


AD-A168 744 AUTEC CABLE ROUTE SURVEY ANDROS ISLAND BAHAMAS SITES 1 2/1 2 AND 7(U) TRACOR MARINE PORT EVERGLADES FL OCCENT TECHNOLOGY DIV 10 JUN 83 CHES/NAVFAC-FPO-8362 N99690-81-D-5278 F/G 8/10 NL



Mile termina probability







AUTEC CABLE ROUTE SURVEY ANDROS ISLAND, BAHAMAS SITES 1, 2 and 7


Submitted to:

Naval Facilities Engineering Command

Ву

Tracor Marine, Inc.

10 June 1983



Ocean Engineering

CHESAPEAKE DIVISION
NAVAL FACILITIES ENGINEERING COMMAND
WASHINGTON NAVY YARD
WASHINGTON, DC 20374

Approved for public releases
Distribution Unlimited



AUTEC CABLE ROUTE SURVEY ANDROS ISLAND, BAHAMAS SITES 1, 2 and 7


Submitted to:

Naval Facilities Engineering Command

Ву

Tracor Marine, Inc.

10 June 1983



SELECTE JUN 1 3 1886

DISTRIBUTION STATEMENT A

Approved for public released
Distribution Unlimited

| Unclassified | |
|---|--|
| SECURITY CLASSIFICATION OF THIS PAGE | |
| REPORT DOCUMENTA la. REPORT SECURITY CLASSIFICATION Unclassified | 1b. RESTRICTIVE MARKINGS |
| 2a. SECURITY CLASSIFICATION AUTHORITY | 3. DISTRIBUTION AVAILABILITY OF REP. Approved for public release; distribution is unlimited |
| 2b. DECLASSIFICATION/DOWNGRADING SCHEDULE | |
| 4. PERFORMING ORGANIZATION REPORT NUMBER | 5. MONITORING ORGANIZATION REPORT # FPO 8362 |
| 6a. NAME OF PERFORM. ORG. 6b. OFFICE SYM Tracor Marine, Inc. | 7a. NAME OF MONITORING ORGANIZATION Ocean Engineering & Construction Project Office CHESNAVFACENGCOM |
| 6c. ADDRESS (City, State, and Zip Code) | 7b. ADDRESS (City, State, and Zip) BLDG. 212, Washington Navy Yard Washington, D.C. 20374-2121 |
| 8a. NAME OF FUNDING ORG. 8b. OFFICE SYM | 9. PROCUREMENT INSTRUMENT INDENT # N00600-81-D-5270 |
| 8c. ADDRESS (City, State & Zip) | 10. SOURCE OF FUNDING NUMBERS PROGRAM PROJECT TASK WORK UNIT ELEMENT # # ACCESS # |
| ll. TITLE (Including Security Classificati AUTEC Cable Route Survey Andros Island, Ba | |
| 12. PERSONAL AUTHOR(S) | |
| 13a. TYPE OF REPORT 13b. TIME COVERED FROM TO | 14. DATE OF REP. (YYMMDD) 15. PAGES 83-06-10 37 |
| 16. SUPPLEMENTARY NOTATION | |
| FIELD GROUP SUB-GROUP Atlant Survey | TTERMS (Continue on reverse if nec.) ic Undersea Test & Evaluation Center, ving, Oceanography, Diving, Cable lation, Retrieval & Repair |
| 19. ABSTRACT (Continue on reverse if necessin accordance with Tracor Marine's Op-plan Atlantic Undersea Test & Evaluation Center May 1983, Tracor Marine conducted precision 1, 2 and 7 during May and June 1983. Usin 20. DISTRIBUTION/AVAILABILITY OF ABSTRACT SAME AS RPT. | n of 18 May 1983 and the u.S. Navy's C Operations Directive 83-202 of 24 On bathymetric surveys at Autec Sites Ong the LCU 1647 as a survey (Con't) |
| 22a. NAME OF RESPONSIBLE INDIVIDUAL Jacqueline B. Riley DD FORM 1473, 84MAR | 22b. TELEPHONE 22c. OFFICE SYMBOL 202-433-3881 SECURITY CLASSIFICATION OF THIS PAGE |

BLOCK 19 (Con't)

platform, the survey equipment consisted of an EDO Model 4077 Narrow Beam Towed Bathymetric System, a Decca Trisponder Navigation System and an HP 9825 - based data acquisition system.

The survey at Site 1, consisting of five sounding lines running perpendicular to the bottom contours, was completed on May 30. The measurements at Site 2 were completed on May 31 and consisted of ten perpendicular runs. on June 3 at Site 7, three perpendicular lines were completed with two 2nm by 1nm grids developed at the eastern and westernmost areas. Aside from minor navigational problems and delays on June 3, no difficulties were encountered in the conduct of this survey, and the project was completed several days ahead of schedule.



FINAL REPORT

AUTEC CABLE ROUTE SURVEY

ANDROS ISLAND, BAHAMAS
SITES 1, 2 AND 7

Submitted to:

NAVAL FACILITIES ENGINEERING COMMAND

BUILDING 200

WASHINGTON NAVY YARD

WASHINGTON, DC 20374

CONTRACT NUMBER N00600-81-D-5270

TRACOR MARINE, INC.
JOB NUMBER 723511

10 June 1983

Approved (00

Edward Clausner Vice-President

| Accesi | on For | \ | |
|--------------------|---------------------|---|--|
| NTIS DTIC | CRA&I | | |
| Unannounced | | | |
| Justific | ation | | |
| By Distribution / | | | |
| Availability Codes | | | |
| Dist | Avail and Specia | | |
| A-1 | | | |

TABLE OF CONTENTS

| SECTION | <u>!</u> | | PAGI |
|---------|----------|--|------|
| 1.0 | Sur | mary | . 1 |
| 2.0 | Eve | ent Log | . 7 |
| 3.0 | Nav | vigation | . 10 |
| 4.0 | Sou | undings | . 12 |
| 5.0 | Dat | ta Processing | . 14 |
| 6.0 | Del | liverables | . 18 |
| 7.0 | Cor | ncluding Remarks | . 20 |
| APPENDI | CES | (Separately packaged) | |
| | Α. | Original Bathymetric Analog Records. | |
| | В. | Original Data Acquisition Records. | |
| | C. | Original (and two copies) Tracor Marine | |
| | | Sounding Logs. | |
| | D. | Original (and two copies) Tracor Marine | |
| | | Watch Logs. | |
| | Ε. | Developed Sounding Sheets at 1:5000 scale | |
| | | for each area surveyed (Original mylar pla | ıs |
| | | two copies of each). | |
| | F. | Developed Vessel Track Sheets at 1:5,000 | |
| | | scale for each area surveyed (original | |
| | | drafting film plus two copies of each). | |
| | G. | Developed 1:1 scale Vertical Profiles of | |
| | | each Sounding Run at Sites 1 and 2 (original | nal |
| | | drafting film plus two copies of each). | |
| | E. | Developed 5:1 scale Vertical Profile Compa | ari- |
| | | sons of Sounding Runs at Sites 1 and 2 | |
| | | (original drafting film plus two copies of | F |
| | | each). | |



1.0 SUMMARY

In accordance with Tracor Marine's Op-plan of 18 May 1983 and the U.S. Navy's Atlantic Undersea Test and Evaluation Center Operations Directive 83-202 of 24 May 1983, Tracor Marine conducted precision bathymetric surveys at Autec Sites 1, 2 and 7 during May and June, 1983. Using the LCU 1647 as a survey platform, the survey equipment consisted of an EDO Model 4077 Narrow Beam Towed Bathymetric System, a Decca Trisponder Navigation System and an HP 9825 - based data acquisition system. The Tracor Marine Survey Team was composed of the following individuals:

Dr. Lanny Yeske, Project Manager

Mr. Dennis Kembro, Project Coordinator

Mr. Patrick Sanders, Hydrographer/
 Cartographer

Mr. Calib Magruder. Cable Route Engineer

Mr. Dallis Copeland Acoustic Technician

The survey at Site 1, consisting of five sounding lines running perpendicular to the bottom contours, was completed on May 30. The measurements at Site 2 were completed on May 31 and consisted of ten perpendicular runs. On June 3 at Site 7, three perpendicular lines were completed with two 2nm by 1nm grids developed at the eastern and westermost areas. Aside from minor navigational problems and delays on June 3, no difficulties were encountered in the conduct of this survey, and the project was completed several days ahead of schedule.




The purpose of this document is to present technical information on the procedures used by Tracor Marine to conduct the survey and to reduce the data as well as to formally transmit to the Naval Facilities Engineering Command the following deliverables:

- · Original Bathymetric Analog Records
- Original Data Acquisition Records.
- · Original Tracor Marine Sounding Logs.
- · Original Tracor Marine Watch Logs.
- Developed Sounding Sheets at 1:5,000 scale for each area surveyed (original mylar plus two copies of each).
- Developed Vessel Track Sheets at 1:5,000 scale for each area survey (original drafting film plus two copies of each)
- Developed 1:1 scale Vertical Profiles of each sounding run at Sites 1 and 2 (original drafting film plus two copies of each).
- Developed 5:1 scale Vertical Profile Comparisons of sounding runs at sites 1 and 2 (original drafting film plus two copies).

The following four pages provide photographs of the LCU 1647 laboratory and towfish rigging configurations as well as the specific tide staff and reef locator systems employed for this survey.





LCU 1647 LABORATORY



LABORATORY TECHNICIANS









LABORATORY SUPERVISORS






TIDE STAFF-AUTEC PIER




REEF LOCATOR





TOWFISH RIGGING



DATA COLLECTION



| 2.0 EVENT LOG | |
|---------------|---|
| 15 March 1983 | Conducted initial technical discussions with NAVFAC and NUSC. |
| 31 March 1983 | Pre-site visit by Tracor Marine to Autec Sites. |
| 21 April 1983 | NAVFAC/NUSC Tasking. |
| 18 May 1983 | Tracor Marine Op-plan completed. |
| 24 May 1983 | AUTEC Operations Directive completed. |
| 25 May 1983 | Final planning conference with NAVFAC, NUSC and Tracor Marine in Fort Lauderdale. |
| 26 May 1983 | Personnel and equipment arrive AUTEC. 1530 meeting at AUTEC Command and Control to update the operational plan. |
| 27 May 1983 | Completed loading of equipment on LCU 1647. Tide staff installed on AUTEC pier. |
| 28 May 1983 | Conducted sea trials. All navigation and sounding equipment operating normally. |



| 29 May 1983 | Interim array retrieval operations. | | |
|-------------|-------------------------------------|--|--|
| | No survey operations planned or | | |
| | conducted. | | |

| 30 May 1983 | Conducted and completed bathymetric |
|-------------|--------------------------------------|
| | survey Site 1 from 1350 to 1850 |
| | with 5 lines perpendicular to bottom |
| | contours. All equipment operating |
| | normally. |

| 31 May 1983 | Conducted and completed bathymetric |
|-------------|--------------------------------------|
| | survey Site 2 from 0735 to 1815 with |
| | 10 lines run perpendicular to bottom |
| | contours. All equipment operating |
| | normally. |
| | |

| 1 June 1983 Weather Da | ау. |
|------------------------|-----|
|------------------------|-----|

| 2 | June | 1983 | Weather | Day. |
|---|-------|------|---------|------|
| 4 | o une | 1703 | Weather | Day. |

| 3 June 1983 | LCU underway 0200 for transit to |
|-------------|--------------------------------------|
| | Site 7. Navigation problems delay |
| | survey start from 1000 to 1327. Sur- |
| | vey commences but intermittent navi- |
| | gation problems continue. |

At 1410, LCU via AUTEC informs Tracor Marine in Fort Lauderdale of navigation difficulties and requests replacement trisponder system be sent ASAP. At 1530, replacement unit is



3 June 1983 (Cont'd) loaded aboard AUTEC plane in West Palm Beach and arrives AUTEC at 1830. Site 7 survey completed at 2123.

4 June 1983

LCU 1647 returns AUTEC Base. Vessel demobilization. Tracor Marine personnel and equipment return to Fort Lauderdale at 1530. Data analysis and final report preparation continues.

10 June 1983 Final report and analysis forwarded to NAVFACENGCOM.



3.0 NAVIGATION

The NUSC supplied Decca Trisponders and an HP 9825 - based data acquisition system were used to position the LCU during sounding operations. For the survey at Site 1, Trisponder antennas were located at Sites 1 and 2. For survey work at Site 2, Trisponder antennas were installed at Sites 1 and 3. At Site 7, antennas were positioned at Sites 6 and 7. Geographic positions (GP), antenna heights and Universal Transverse Mercator (UTM) coordinates for the shore NAVAID sites are given in Table 1.

The horizontal offset between the ship's Trisponder antenna and the towed transducer was measured daily and appropriate offsets were applied to the navigational fixes.

It should be noted that for the survey at Site 2, the use of Trisponders at Sites 1 and 3 provided less than optimum angles of intersection for positioning. This was most pronounced in near shore areas where the angle of intersection approached 10 degrees.



TABLE 1

AUTEC ANTENNA LOCATIONS

| Site 1 N24 ^o 42' 20.97" | N 2,735,041.749 |
|--------------------------------------|-----------------|
| W77 ⁰ 45' 54.89" | E 220,223.007 |
| HT = 90' EST = 27.4 m | |
| | |
| Site 2 N24 ^o 29' 53.97" | N 2,711,958.265 |
| W77 [°] 43' 10.55" | E 224,389.325 |
| HT = 66.3' = 20.2 m | |
| | |
| Site 3 N24 ^o 20' 17.0743" | N 2,694,131.454 |
| W77 ⁰ 40' 59.9682" | E 227,723.084 |
| HT = 60' = 18.3 m | |
| _ | |
| Site 6 N24 ^O 00' 23.69' | N 2,657,112.857 |
| W77 [°] 31' 43.55" | E 242,749.188 |
| HT = 8.550 m | |
| | |
| _ | N 2.645,255.235 |
| W77 ⁰ 29' 19.46" | E 246,614.703 |
| HT = 23.979 m | |

Spheroid: Clarke 1866 (NAD 1927)



4.0 SOUNDINGS

Soundings were taken using the Edo Model 4077 Narrow Beam Towed Bathymetric System, supplied by Tracor Marine. All soundings were taken using the 40kHz, 5° narrow beam transducer. This transducer provided the resolution and definition needed when surveying perpendicular to the steep walls off Andros Island. The transducer depth was measured daily and is incorporated in the sounding on the smooth sheets. A heave compensator was also supplied by Tracor Marine but was not used due to a calm sea state and stable towing conditions.

Tide corrections. ranging from 0 to 2 feet, were applied to all soundings under 600 feet. A tide staff was erected at the AUTEC Pier and observed to establish correlations with predicted tide information from published NOAA tide tables. Variances of observed versus predicted tide heights were less than .2 feet. Predicted tides were used to adjust soundings to the Mean Low Water datum.

At Site 7, where it was feasible to compare soundings at principal line and crossline intersections, total agreement in soundings was observed.

In several areas while traversing steep bottom gradients, the digitizer "gate" could not accurately track the bottom. This



resulted in having to manually scale the analog trace to obtain depth data, however, this did not pose much of a problem. Part of the digitizer's trouble was due to the increasing speed of the survey vessel. At the recommended towing speed of 4-5 knots, the digitizer performed well. By the end of the survey, the ship speed was approximately 7 knots and the digitized data was degraded in areas with steep gradients.



5.0 DATA PROCESSING


Sounding and Track Sheets are UTM projections using the Clarke 1866 Spheroid North American Datum of 1927. All sheets are at a scale of 1:5,000. The Sheet layout for the surveys at Sites 1,2 and 7 are given in Figures 1, 2 and 3 respectively.

For Site 1, Sheet 1A contains four sounding lines run perpendicular to the bottom contours. Sheet 1B contains a fifth line. For Site 2, Sheet 2A contains nine lines (two at line 5) run perpendicular to bottom contours. Sheet 2B contains an additional line run at High Cay. For Site 7, Sheet 7A contains the westernmost of the two grids run in this area. Sheets 7B and 7C contain three lines run perpendicular to bottom contours while sheet 7C also contains the eastern grid.

In constructing the sounding and vessel track sheets Red and Green Trisponder values were taken from the HP 9825 computer printout and converted to UTM coordinates for the ships's position at one minute intervals. These fixes were then plotted on the UTM projection. The transducer offset (variable for each Site) was then applied to obtain the correct position of the transducer.

Digitized soundings on the computer printouts were also compared to the analog trace to verify their correctness. False echos and noise, which had been digitized as bottom, were edited out. Soundings were then corrected for transducer depth and tides, and plotted in their correct location on the sounding sheets. Soundings were contoured at 100 feet, 200 feet, and every 200 feet thereafter.

SITE I






Figure 2





Figure 3



6.0 DELIVERABLES

The following deliverables (separately packaged) are being supplied to Naval Facilities Engineering Command for use or distribution as desired:

Appendix A: Original Bathymetric Analog records

from EDO Model 4077 System at Sites

1, 2, 7 and during sea trials.

Appendix B: Original Data Acquisition System

Records from NUSC supplied HP 9825

based system.

Appendix C: Original and two copies of Tracor

Marine's Sounding Logs at Sites 1, 2

and 7.

Appendix D: Original and two copies of Tracor

Marine's Watch Logs at Sites 1, 2 and

7.

Appendix E: Original and two copies of Sounding

Sheets 1A, 1B, 2A, 2B, 7A, 7B and 7C

plotted on .007" thick Herculene

Drafting Film.

Tracor Marine

6.0 DELIVERABLES (Cont'd)

Appendix F: Original and two copies of Vessel

Track Sheets 1A, 1B, 2A, 2B, 7A, 7B

and 7C plotted on .025" thick Albanene Drafting Film with preprinted precise millimeter grid.

Appendix G: Original and two copies, 1:1 horizontal

to vertical scale, of Vertical Profiles

of each Sounding Run at Sites 1 and 2.

Appendix H: Original and two copies, 5:1 horizon-


tal to vertical scale, of Vertical Pro-

file Comparisons of Sounding Runs at

Sites 1 and 2.


7.0 CONCLUDING REMARKS

The fact that this project was completed ahead of schedule and under-budget reflects the amount of assistance and cooperation rendered to Tracor Marine. As such, we would like to express our sincere appreciation and gratitude to the numerous individuals from NAVFAC, NUSC, RCA, LCU 1647 and AUTEC (both on Andros Island and in West Palm Beach) who contributed significantly to this effort and its successful completion.



ACC | PASS | ACC


Ì




Ì


5.5

SITE 2 TRACK 2 SHEET 2A



ń







ħ

201 200


1.4





R

S




-

200 BSS


Î


-


The second of the control of the con





Ü











なるというかんかい